

**KEYED NOTES:**

- 1) OWNER TO CLEAN AND ABANDON EXISTING STRUCTURE IN-PLACE
- 2) FILL PIPE WITH LEAN CONCRETE
- 3) PLUG EAST INLET END AND FILL DOWNSTREAM PIPE WITH LEAN CONCRETE
- 4) ABANDON EXISTING MANHOLE PER WSDOT STANDARD SPECIFICATION 7-05.3(2). FILL DOWNSTREAM PIPE WITH LEAN CONCRETE
- 5) REMOVE EXISTING MANHOLE, GRATE, PIPE, VALVES & APPURTENANCES. DISPOSE OF OFF-SITE.
- 6) FILL 12" DI PIPE FROM EXISTING MANHOLE TO CLEANOUT WITH LEAN CONCRETE
- 7) OWNER TO REMOVE AND SALVAGE PUMPS, BLOWERS AND PIPING FROM BASEMENT OF EXISTING BUILDING. CONTRACTOR TO PLUG PIPE STUBS W/CONCRETE, COORDINATE WITH OWNER.
- 8) CUT OFF 6" PIPE 1 FT FROM BUILDING, PLUG PIPE STUB WITH CONCRETE
- 9) REMOVE MIXING MH #2 AND DISPOSE OF OFF-SITE.
- 10) REMOVE EXISTING OVERHEAD LIGHT.
- 11) REMOVE EXISTING CLEANOUT AND DISPOSE OF OFF-SITE
- 12) REMOVE EXISTING 12" DI PIPE FROM THE CLEANOUT TO THE CLARIFIER AND DISPOSE OF OFF-SITE
- 13) PLUG CLARIFIER INVERT WITH CONCRETE
- 14) REMOVE CLARIFIER MECHANICAL ITEMS, APPURTENANCES AND 8" PIPE AND DISPOSE OF OFF-SITE. REMOVE AND DISPOSE UPPER 4 FT. FILL WITH BANK RUN GRAVEL
- 15) DISCONNECT FROM 2" WM (GFP) AND DISPOSE OF OFF-SITE
- 16) DRAINER EXISTING CHLORINE CONTACT CHAMBER AND PLUG 6" PIPE PENETRATION WITH CONCRETE. FILL STRUCTURE WITH BANK RUN GRAVEL AND CAP WITH 6" OF CONCRETE. SEE DWG C501 FOR DETAILS.
- 17) OWNER TO RELOCATE SATELLITE DISHES
- 18) OWNER TO REMOVE AND SALVAGE EXISTING GATE VALVES
- 19) PRIOR TO REGRADING, DISPOSE OF ALL SLUDGE TO LANDFILL
- 20) REMOVE CAU WALLS AND DISPOSE OF OFF-SITE
- 21) REMOVE 6" PIPE AND DISPOSE OF OFF-SITE
- 22) REMOVE FLOW METER AND SALVAGE TO THE OWNER
- 23) REMOVE EXISTING PUMP AND SALVAGE TO THE OWNER
- 24) REMOVE EXISTING HANDRAIL AND DISPOSE OF OFF-SITE
- 25) RELOCATE SAMPLER TO NEW HEADWORKS. SEE DWG C3.
- 26) REMOVE 4" AND 6" DRAIN LINES FROM SLUDGE DRYING BED UP TO CLEANOUT AND DISPOSE OF OFF-SITE
- 27) REMOVE SECTION OF PIPE UNDER NEW UV BLDG AND REROUTE PER C501

MECHANICAL/ELECTRICAL/STRUCTURAL TO BE REMOVED AND DISPOSED OF OFF-SITE


NOTE:  
CONTRACTOR TO MAINTAIN SERVICE OF ANY AND ALL EXISTING WWTP FACILITIES UNTIL NEW FACILITIES ARE MADE OPERATIONAL. WORK MAY INCLUDE TEMPORARY RELOCATION OF AN EXISTING FACILITY. COORDINATE WITH ENGINEER.

CALL THREE BUSINESS DAYS BEFORE YOU DIG  
1-800-424-5555

PLAN  
SCALE 1"=20'

COLUMBIA RIVER

REVISIONS



<p><b>HAMMOND COLLIER WADE LIVINGSTONE</b></p>		<p>CITY OF ENTIAI 2007 WASTEWATER TREATMENT FACILITIES IMPROVEMENTS</p>		<p>JOB NO. 0523004-03</p>
		<p>DEMOLITION SITE PLAN</p>		<p>DRAWING NO. D1</p>
<p>DESIGNED BY: RS</p>	<p>CHECKED BY: MR. DG</p>	<p>DATE PRINTED: 08/20/07</p>	<p>SCALE: AS SHOWN</p>	<p>SEATTLE (206) 632-5664</p>
<p>GENERAL NOTES</p>	<p>REVISIONS</p>	<p>DATE PRINTED: 08/20/07</p>	<p>SCALE: AS SHOWN</p>	<p>ONAK (509) 826-5861</p>
<p>SEATTLE (206) 632-5664</p>		<p>ONAK (509) 826-5861</p>		<p>LAKEMOOD (253) 472-1992</p>